

# UNOFFICIAL COPY

# 192

Contact the Bayfield County Register of Deeds Office to obtain an official copy of this document.

EXISTING CONCRETE MONUMENT  
3.39' N. AND 7.93' E. OF  
THEORETICAL SECTION AS PER  
DESCRIPTION.

## BAYFIELD COUNTY CERTIFIED SURVEY MAP NO. 202116

PART OF GOV. LOT 5, SECTION 17, T. 43 N., R. 7 W.

62.5 17-43-7

2/2

### LEGEND


- - Existing 2" x 30" galv., capped iron pipe, found in place.
- - Existing 1 1/2" diameter iron bar, found in place.
- - Existing 3/2" diameter round concrete monument, with 1/2" iron rod in center, found in place. (Locally accepted as property corner.)
- - 1" x 30" iron pipe with plastic cap, stamped "SCHMIDT S-1059", set this survey.
- Denotes existing fence line.
- - - Denotes centerline of 15-foot wide driveway easement for access to lands lying North of this Certified Survey.
- Heavy line denotes this survey.

Date: Dec. 22, 1976  
 REVISED: Dec. 31, 1976  
 Scale: 1 inch = 100 feet



TRUE BEARINGS

N



APPROVED

Bayfield County Zoning Comm.


By *Jared E. Schaefer*

Date 1-12-77 App# 268 Map#

**RESTRICTIONS:** No buildings for human habitation or installation of soil absorption systems for septic effluent disposal will be permitted on Outlot 1, unless future regulations and the division of Health so permit.

## OUTLOT 1

137648 sq. ft.



G.T.H. M

UNPLATTED LANDS

UNPLATTED LANDS

W. 1/4 Cor., Sec. 17, T. 43 N., R. 7 W. UNPLATTED LANDS  
 E. 1/4 Cor., Sec. 17 UNPLATTED LANDS  
 PLAT OF CRESTVIEW ACRES

# UNOFFICIAL COPY

Contact the Bayfield County Register of Deeds  
Office to obtain an official copy of this document.

Sheet No. 2

BAYFIELD COUNTY CERTIFIED SURVEY MAP NO. \_\_\_\_\_

Part of Gov. Lot 5, Section 17, T. 43 N., R. 7 W.

## SURVEYOR'S CERTIFICATE

I, James J. Schmidt, Registered Land Surveyor, hereby certify that, by the direction of Harry Wirth, I have surveyed, described and mapped the land parcels which are represented by this Certified Survey Map;

that the exterior boundary of the land parcels surveyed and mapped is described as follows:


Commencing at the West  $\frac{1}{4}$  corner of Section 17, T. 43 N., R. 7 W., thence S  $86^{\circ}19'19''$  E along the East-West  $\frac{1}{4}$  line of Section 17, 1307.81 feet to the point of beginning; thence N  $2^{\circ}06'09''$  W, 300.93 feet; thence S  $86^{\circ}12'53''$  E, 1308.68 feet; thence S  $2^{\circ}15'33''$  E, 298.56 feet to the East-West  $\frac{1}{4}$  line of Section 17, thence N  $86^{\circ}19'19''$  W, 1309.25 feet to the point of beginning.

that this Certified Survey Map is a correct representation of the exterior boundary surveyed and described, that I have fully complied with the current provisions of Chapter 236.34, Wisconsin Revised Statutes, and the Subdivision Control Ordinance of Bayfield County, Wisconsin in surveying and mapping same.

Certified this 22nd day of December, 1976, at Park Falls, Wisconsin

Revised this 31st day of December, 1976.

Signed: James J. Schmidt  
James J. Schmidt, Land Surveyor  
Wisconsin Registration No. S-1059



APPROVED:

Date: \_\_\_\_\_

Bayfield County Zoning Administrator

311692