


# UNOFFICIAL COPY

Contact the Bayfield County Register of Deeds Office to obtain an official copy of this document.

## BAYFIELD CO. CERTIFIED SURVEY NO. 000500

LOCATED IN G.L. 12, SEC. 27-T44N-R6W, TOWN OF GRANDVIEW, BAYFIELD COUNTY, WISCONSIN.





SCALE - 1" = 100'

⊙ = EX. IRON SURVEY MON.

○ = SET 1" x 24" IRON PIPE, MIN. WT. 1.13 LBS./LIN. FT.

BEARINGS ARE REFERENCED TO SOUTH LINE OF SE 1/4, SEC. 27-T44N-R6W. N89°-32'W



Gov. Lot 12 27-44-6

333

# UNOFFICIAL COPY

Contact the Bayfield County Register of Deeds  
Office to obtain an official copy of this document.

SURVEYOR'S CERTIFICATE: (1 - 3)

I, Duane A. Marten, Registered Land Surveyor, hereby certify:

That I have surveyed, divided and mapped that part of Gov't. Lot 12, Sec. 27-T44N-R6W, Town of Grandview, Bayfield County, Wisconsin, bounded and described as follows:

Commencing at the SE corner of said Sec. 27; thence N89°-32'W along the South line of the Sec., 1414.25 feet; thence N3°-25'W along the Easterly line of Triangle Road, 974.56 feet; thence N1°-26'W along said Easterly line, 88.45 feet to the point of beginning; thence continuing N1°-26'W, 460.57 feet; thence N15°-24'W along said Easterly line, 105.22 feet to a point 60 feet, more or less, from the water's edge of an outlet to Trapper Lake; thence N88°-46'-30"E along a meanderline, 163.70 feet; thence S21°-03'-30"E along said meanderline, 393.54 feet to a point 50 feet, more or less, from the water's edge of Trapper Lake; thence S53°-16'-52"W, 331.35 feet to the Easterly line of Triangle Road and the point of beginning. Including all lands lying between the above described meanderline and the water's edge of the outlet to Trapper Lake and also between the above described meanderline and the water's edge of Trapper Lake itself. Subject to all easements and reservations of record.

That such plat is a correct representation of all exterior boundaries of the land surveyed and the subdivision thereof made.

That I have made such survey, land division and plat by the order and under the direction of Mr. Keith Benedict.

That I have fully complied with Chapter 236.34 of the Wisconsin Statutes and the subdivision regulations of Bayfield County to the best of my knowledge and belief.

Dated this 26 day of April, 1984.

Duane A. Marten

DUANE A. MARTEN, REGISTERED LAND SURVEYOR, S-1029  
VACATIONLAND SURVEYOR'S, INC.  
SOLON SPRINGS, WIS.

APPROVED: BAYFIELD CO. ZONING COMMITTEE  
DATED: 30 APRIL 1984  
DAVE LEE David K Lee ADM.

